

concrete construction

MARCH 1958

VOL. 3, NO. 3

EDITED FOR

All who are concerned with quality, JOB PLACED CONCRETE (including prestress, tilt-up, lift slab, and thin-shell)—its production, handling, forming, reinforcing, placing, finishing, and curing: CONCRETE CONTRACTORS; GENERAL CONTRACTORS; INDUSTRIAL CONSTRUCTION AND MAINTENANCE MEN; ENGINEERS; ARCHITECTS; STATE HIGHWAY ENGINEERS; READY-MIXED CONCRETE PRODUCTS.

COPIES DISTRIBUTED

28,425

FEATURES

9 GANTRIES PLACE SITE CAST CONCRETE GIRDERS

With site casting accounting for an increasing volume of prestressed concrete work, contractors will be interested in this account of how a Denver firm solved the knotty problem of placing 96-ton girders for a highway and railroad bridge construction project.

10 FRANK LLOYD WRIGHT'S GUGGENHEIM MUSEUM

The general contractor for one of the most complex and daring poured concrete buildings ever designed tells how some of the more perplexing problems were dealt with. Rigid controls applied to every stage of the concreting operations have produced one of the finest examples of concrete construction to be found anywhere in the world.

**15 COMPLETED WORK CARRIES
WEIGHT OF FORMS AND CONCRETE**

The use of a new steel form design enabled an Eastern contractor to support over 300 tons of formwork and concrete high in the air without falsework. The result: Substantial savings on a \$6-million sub-structure contract for a bridge on the New York State Thruway.

21 WIDTH OF CRACKS IN REINFORCED CONCRETE

We formerly believed that cracks in reinforced concrete were about the same width near the surface of the reinforcing steel as at the outside surface of the concrete. Here is some important evidence that there is actually less steel exposed to atmospheric corrosion under these circumstances than we had thought.

22 TILT-UP TECHNIQUES FOR SMALL PANELS


Some interesting findings of a study launched to develop economical methods of constructing relatively small fireproof buildings. One contractor describes the resulting technique for tilt-up work as the easiest way to handle concrete he has ever seen.

DEPARTMENTS


4 BOOK REVIEWS

20 EQUIPMENT, TOOLS, MATERIALS

36 INDEX TO ADVERTISERS



Concrete job pays extra profits for careful planning of concrete handling



Concrete construction on this 300' x 600' airplane hangar required two types of concrete handling—(1) bulk handling for columns, foundation and 17" thick walls and (2) slower paced handling for thin finished floor slabs. The problem was—how to prevent delays and inefficiencies in one or both placement jobs.

The answer here was to divide the work and use two separate crews and two concrete handling methods simultaneously.

First, two Gar-Bro Buckets per crane were used for the bulk placing. While one bucket was being filled, the other was placing concrete. Thus with a minimum crew, a fast pace was maintained.

Second, Gar-Bro Floor Hoppers and a fleet of Concrete Carts supplied the slab work. The concrete buckets load the floor hoppers for cart charging and alternate for direct column pouring, thus holding the balance of the operation.

In this way there were no delays and no interruptions of work. A steady delivery of concrete by ready mix trucks provided maximum efficiency.

Since every wasted minute costs money on a concrete job and delays cost more than equipment, it pays to plan each job properly. Many similar innovations are described in the regular issues of Gar-Bro Concrete News and the Gar-Bro Concrete Manual, available on request.

GAR-BRO MANUFACTURING CO.

Los Angeles, California • Peoria, Illinois

General Offices:

2415 East Washington Blvd.

Los Angeles 21, California



GAR-BRO

The world's most complete line of
**CONCRETE HANDLING
EQUIPMENT**



CONCRETE CONSTRUCTION MAGAZINE

139 No. Clark St. Chicago 2, Illinois
ANdover 3-4329

WILLIAM M. AVERY
editor and publisher

JOHN M. ENGLE
co-publisher

AGATHA COTTON
distribution manager

CLARISSA McKNIGHT
product news editor

JOHN DEMLING
contributing editor

pacific coast representatives

DUNCAN A. SCOTT & CO.

Los Angeles 57

1901 West 8th St., Dunkirk 8-4151

San Francisco

85 Post Street, Garfield 1-7950

Published monthly and copyrighted© 1958 by Concrete Construction Magazine. The cover design and contents of CONCRETE CONSTRUCTION are fully protected by copyrights, and must not be reproduced in any manner or form. Subscription price: Single copies, \$1.00; \$5.00 per year (U.S.A.); \$10.00 per year (Foreign). Accepted as controlled circulation publication at Chicago, Illinois.




CONCRETE CONSTRUCTION

PLASTIMENT CONCRETE DENSIFIER

Specified

FOR PHILADELPHIA'S GORGAS LANE BRIDGE



Plastiment concrete in 7 foot deep beams is being revibrated before deck is placed.

This unusual monolithic prestressed beam and slab design resulted from alternate bids permitted by Philadelphia's progressive Department of Streets* . . . Savings of more than 20% over conventional steel design were passed on to the taxpayers.

Each 120 ft. long span, 34 ft. wide; including two traffic lanes, sidewalk, and half of the center median strip was concreted in one continuous 260-yard operation . . . Since 8-10 hours elapsed during placement, Plastiment was specified to control initial set. Plastiment provided these additional benefits: better compaction, greater density, and faster development of stressing strength.

Your clients will benefit from the better structural quality of Plastiment concrete . . . Specify Plastiment for your next job . . . Write for Bulletin PCD.

AD 26-7

*David M. Smallwood, Street Commissioner
Neel W. Willis, Chief Bridge Engineer

The Preload Company, Inc., New York City—Consulting Engineers
The Conduit & Foundation Corporation, Philadelphia—Contractor

SIKA CHEMICAL CORPORATION

PASSAIC, NEW JERSEY

DISTRICT OFFICES: BOSTON • CHICAGO • DALLAS
• DETROIT • PHILADELPHIA • PITTSBURGH
• SALT LAKE CITY • WASHINGTON • DEALERS IN
PRINCIPAL CITIES—AFFILIATES AROUND THE WORLD





SPEED UP finishing on small concrete jobs

A Complete Line of Concrete Construction Equipment.



Vibrating Screeds



Grinders



Roto-Trowels



Vibrators

The 1954 Building Estimator's Reference Book says it takes 2.6 man hours to finish 100 sq. feet of concrete by hand. The Stow G29 Roto-Trowel can float and finish the same area in about 1 man hour, making it more than twice as fast as by hand.

This is one of the reasons why these trowels are becoming so popular with smaller contractors throughout the country for small jobs such as cellars, patios, garage floors and sidewalks.

Builders also like the exclusive Stow Dead-Man clutch control; merely by letting go of the clutch the operator stops the blades *without* stopping the engine. This is an important safety feature.

Stow Roto-Trowels are easier to start too. The manual clutch control makes it possible to start at full throttle if necessary . . . this is impossible with a centrifugal clutch unless the belt is removed.

Stow Roto-Trowels are built for safety, dependability, and long life . . . built to produce excellent concrete finishes.

Look up your nearest distributor in the yellow pages of your phone book under "Concrete Vibrators" or

MAIL THIS COUPON TODAY!

Stow Manufacturing Co. 354 Shear Street
Binghamton, New York

I'm interested in the Stow Line of Concrete Construction Equipment. Send a complete catalog, and name of nearest distributor.

I am particularly interested in _____

Name _____ Title _____

Company _____

Street _____

City _____ State _____

STOW

Manufacturing Co.
Shear Street
Binghamton, New York

books

Manual of Recommended Practice for Inspection and Testing of Concrete Materials and Concrete. Published by Concrete Industry Board, Inc., 220 East 42nd Street, New York 17, New York. 12 pp. \$0.50.

This small volume may well prove to be a landmark in the Concrete Industry Board's long sustained program to improve the standards of concrete construction work. The document is the work of a joint committee of testing laboratories in the metropolitan New York area appointed by the Concrete Industry Board. It is based on the experience of the committee members and on practice and code requirements in the New York area. The committee has clearly and forthrightly stated certain principles which they believe should be followed in the inspection and testing of concrete and concrete materials. For example, it recommends that the owner or architect and not the contractor should employ a qualified testing laboratory to carry out the requirements of the specifications. It clearly enunciates the principle that as a professional service the laboratory should not be engaged on the basis of competitive bidding.


Section A of the manual covers such subjects as the preliminary test of materials and mix design, the duties of batch plant inspector and project site inspector, and covers in detail such matters as casting, protecting and storing concrete test cylinders on project sites as well as in the laboratory. Section B covers a discussion of controlled concrete versus average concrete, gives recommendations for the procedures to be followed in producing controlled concrete in the city of New York, and includes suggested specifications.

Design of Tilt-Up Buildings. By F. Thomas Collins. Published by Know How Publications, P. O. Box 208, San Gabriel, California. 162 pp. Ills. \$12.50 postpaid U. S. A.


This is the third volume which Mr. Collins has written on the general subject of tilt-up construction, the first having carried the title "Manual of Tilt-Up Construction" and the second the title "Building with Tilt-Up." The preface points out that tilt-up construction has developed to the stage that the general understanding of its principles

NEW STEEL STAKING PACKAGE by **dee** for the concrete contractor


**SLASH
COSTS**



flat work



footings



curbs


dee CONCRETE PRODUCTS CO.

Licensed Manufacturer

670 N. Michigan Ave., Chicago 11, Ill.
MOhawk 4-3664

Copyright 1958

MARCH 1958



The dee Package

- Sets up 5 to 10 times faster than wood
- No material clean-up after stripping
- All items can be used indefinitely
- Safe — no splitting, no splintering
- Mechanizes your ordinary wood forms

The dee Steel Stake

- A solid round rod — properly pointed
- 12 nail holes — 1" o.c. at 30° points
- 1' to 5' long — standard or heavy duty
- 2 nails fasten it — rotation loosens it

The dee Steel Spreader Bar

- Fast, accurate forming, without measuring
- 1 nail locks it securely to the form board

The dee Steel Brace or Kicker

- Rides the steel stake for final adjustment
- 2 nails lock it firmly to the form board

COMPARE wooden stakes, good for 3 to 5 uses, lots of nails, clean-up after each use. SEE the savings in lumber, nails, plus continued material and labor savings. TRY dee Products and make more money on your concrete work.

The Federal District Court in Washington, D. C. has decreed that the inventor is entitled to a U. S. Patent on this stake. Formal issuance of a patent is expected soon.


dee CONCRETE PRODUCTS CO.

670 N. Michigan Ave., Chicago 11, Ill., MOhawk 4-3664

Send additional information on dee Products.

Name _____
Company _____
Address _____
City _____ Zone _____ State _____

SYNTRON "Vibra-Flow" VIBRATORY FEEDERS



Two SYNTRON Feeders feeding material to belt conveyor. First feeder with overhead magnet feeding limestone screenings, second with below deck magnet feeding sand.

**add new economy and efficiency
to your bulk materials handling.**

SYNTRON Vibratory Feeders provide continuous handle of sand, gravel, cement and other bulk materials in concrete plants all over the country. Combining positive vibration with instant control of flow, they can move bulk materials—hot or cold, damp or dry—smoothly from bins and hoppers to screens, conveyor belts, mixers and other process equipment. By maintaining positive control of materials flow any interruptions in the process cycle are eliminated.

SYNTRON Vibratory Feeders are built in a range of capacities with single, dual or twin and twin dual magnets—above or below deck mounting with tubular or flat pan troughs.

Years of experience in the materials handling field qualifies SYNTRON to act on your problems, both large and small.

cc 258 **Equipment of Proven Dependable Quality**

Syntron can help you with problems involving . . .

Vibrators
(bins, hoppers, chutes)

Vibratory Feeders

Vibratory Screens

Shaker Conveyors

Vibratory Elevator Feeders

Weigh Feeders

Packers and Jolters

Hopper Feeders

Lapping Machines

Rectifiers

(Silicon and Selenium)

a-c to d-c Selenium Rectifier Units

Electric Heating Panels

Electric Heating Elements

Sinuated Wires

Shaft Seals

Electric Hammers

Concrete Vibrators

Paper Joggers

Syntron Sales and engineering service is available from 36 representatives throughout the United States. Take advantage of their willingness to work with you.

For more information write for complete catalog . . . *Free*

SYNTRON COMPANY

323 Lexington Avenue

Homer City, Penna.

books

and methods of design is in demand by design offices and individual engineers and architects throughout the country. The new book, which has been intentionally limited to industrial and commercial buildings, is intended to partially fulfill this demand, the emphasis being on one-story construction but with some two and three-story building being included.

It is noted that at the present time 80 percent of the single-story industrial and commercial buildings in southern California are being constructed by the tilt-up method and that the buildings have been tested by fire, wind, earthquake, flood and blast forces. The author points out that the structural integrity of the method when properly designed has been proved beyond question, but he comments that there still remain problems of joinery, application of prestressing, design standards, code standards, and apprentice instruction.


The volume is generously illustrated with photographs, diagrams and charts, and numerous examples of design calculations are given to illuminate the various principles discussed. For those who are not familiar with field practice in connection with tilt-up, it would seem to be desirable to obtain a copy of the author's book "Building with Tilt-Up" for study along with the new volume.

Proceedings of the World Conference on Prestressed Concrete. Published by World Conference on Prestressed Concrete, Inc., Room 216, 417 Market Street, San Francisco 5, California. 600 pp. Illus. \$10.00.

This is probably the most varied collection of know-how on the subject of prestressing ever assembled in a single volume. Part I covers the 38 papers which were presented orally at the Conference, while Part II presents an additional 26 papers which were prepared for the Conference but not delivered orally because of the crowded schedule.

The Conference brought together scientists, engineers and manufacturers in the field of prestressed concrete, with 1200 delegates from all over the world participating. The Proceedings were edited by J. W. Kelly, T. Y. Lin, A. C. Scordelis and C. C. Zollman.

CONCRETE CONSTRUCTION



...add SOLVAY CALCIUM CHLORIDE to Avoid Costly Delays!

When temperatures vary from 70° down to 50°—it spells "SLOW-UP" which means costly delays in your concreting operations. This drop below 70° sharply decreases strength development and lengthens the waiting period before finishing.

A drop from 70° to 50°, for example, cuts 3-day strength up to 40%. To prevent this, add a low-cost 2% of SOLVAY Calcium Chloride to your concrete.

With this acceleration, concrete poured at 50° has a 3-day strength up to 40% *greater* than ordinary concrete cured at the ideal temperature of 70°!

When you use SOLVAY Calcium Chloride, you do away with overtime finishing, delays in form removal, delays between operations. You save up to 50% on protection time. And you get *better* concrete—increased in *both* early and ultimate strength—with lower water-cement ratio for more moisture-and-wear-resistant concrete.

SOLVAY Calcium Chloride accelerates, but does not change the normal action of portland cement. Tests by the National Bureau of Standards proved its advantages in cold weather concrete construction. It is recommended by leading authorities, including American Concrete Institute and Portland Cement Association.



SOLVAY branch offices and dealers are located in major centers from coast to coast.



HANDY 25 LB. BAG

EASY TO USE

ASSURES ACCURATE MEASURE

For full information, mail coupon!



SOLVAY PROCESS DIVISION

ALLIED CHEMICAL & DYE CORPORATION
61 Broadway, New York 6, N. Y.

Please send—at no cost—your booklet:

- ☐ "When the temperature drops BELOW 50°F, do you know what happens to CONCRETE?"
- ☐ "The Effects of Calcium Chloride on Portland Cement."

NAME

POSITION

COMPANY

PHONE

ADDRESS

CITY ZONE STATE 83-3



AIRLINE HIGHWAY INTERCHANGE handles traffic from Airline Highway, a principal east-west route, and Causeway Blvd., the only direct north-south route in East Jefferson Parish (New Orleans). Built for the

Greater New Orleans Expressway Commission. Engineering and design by Palmer and Baker Engineers, Inc., New Orleans. Louisiana Paving Co., Kenner, La., contractor.

Go-Signs to Civic Progress — two unusual interchanges

NEW ORLEANS and Pittsburgh had the same problem. Converging highways caused progress-choking traffic jams. Each city found the solution in impressive interchanges. Two of their structures present an interesting contrast in design.


The New Orleans Airline Highway Interchange is a compact, symmetrical 4-level design, dominated by a unique elevated traffic circle. It consists of a

6-lane underpass, service roads at grade, intermediate level turning circle with 8 approach ramps, and a 4-lane overpass.


On the other hand, Pittsburgh's Etna Interchange, now under construction, is a seeming maze of roads and ramps. Several miles of roadways will crisscross at multiple levels. Construction problems are unusually tough. Steep hills must be benched out, railroad tracks relocated

and even a stream bed shifted.

Modern traffic requires spectacular highway structures like these, and modern truck mixers to pour them. These highly mobile concrete plants can operate where other equipment can not be used. Their mixing efficiency is guaranteed by Rating Plate, certifying their correct design, capacity and mixing speed and accuracy of water control.



ETNA INTERCHANGE (shown in a model) will pick up traffic from downtown Pittsburgh, a main local artery and two important highway routes. Leonard J. Curran, engineer in charge for Pennsylvania Department of Highways, Richardson, Gordon and Assoc., Pittsburgh, consulting engineers; Latrobe Road Construction Co., Latrobe, Pa., contractor.



You have a right to insist on this Rating Plate. It certifies compliance with the high industry standards maintained for your protection by the Truck Mixer Manufacturers Bureau.

BLAW-KNOX CONSTRUCTION EQUIPMENT DIV.
Mattoon, Ill.

CHAIN BELT COMPANY
Milwaukee, Wis.

CHALLENGE MANUFACTURING CO.
Los Angeles, Calif.

CONCRETE TRANSPORT MIXER CO.
St. Louis, Mo.

CONSTRUCTION MACHINERY CO.
Waterloo, Iowa

THE JAEGER MACHINE COMPANY
Columbus, Ohio

THE T. L. SMITH COMPANY
Milwaukee, Wis.

WESTINGHOUSE TRANSIT MIXER DIV.
Indianapolis, Ind.

WHITEMAN MANUFACTURING CO.
Pocima, Calif.

WILLARD CONCRETE MACHINERY CO., LTD.
Lynwood, Calif.

WORTHINGTON CORPORATION
Plainfield, N. J.

CONCRETE CONSTRUCTION




Photo courtesy of Fresson Corporation

Supporting the 96-ton load of one of the prestressed concrete girders for a bridge near Colorado Springs, Colorado the two gantry cranes at the far right of the picture are moving out on temporary steel trusses which span the distance between adjacent piers. Three of the girders are already in position.

Gantries Place Site Cast Prestressed Concrete Girders

WHEN A. S. HORNER CONSTRUCTION COMPANY, Denver, was awarded a contract recently for the construction of four highway bridges and two railroad bridges within the area of the Air Force Academy north of Colorado Springs, Colorado, it was confronted with a problem in positioning the prestressed concrete girders for the highway bridges following their onsite casting.

A total of 112 post-tensioned girders was employed in the highway bridges. Each girder weighed 96 tons, was 120 feet long and had an overall depth of 5 feet 11 inches. Eight girders, spaced on 9-foot centers, comprised each span of the 88-foot divided highway.

Two 60-ton cranes could have done the moving job, yet they were not readily available in the area. The use of four 30-ton cranes was considered, but this course of action was ruled out because of the roughness of the terrain.

Thus, the following method was developed: Two gantries were constructed, each with a 50-ton chain block. Mounted on rails which extended over the abutment on temporary steel trusses, these gantries, in effect, "straddled" each end of the girder in its casting bed. Subsequently, the gantry chain blocks were hooked onto the lifting loops in each end of the girder, which was then rolled into its final position in the span.

Concrete casting beds were constructed on one of the approaches to each bridge. These casting beds were aligned with the final location of the girders on the piers and abutments. Wooden side forms, fabricated in 20-foot long panels, were used to form the girders. These panels were bolted to inserts in the concrete form soffit at the base and tied across the top. Each panel was used an average of 15 times before major repair was needed.

Both internal and external vibration were used for consolidation.

Each of the girders was fully prestressed and the tendons grouted before removal from the casting bed. The specified 28-day cylinder strength of the concrete was 5,500 psi, a cylinder strength of 4,500 psi being required at transfer. This strength was achieved in an average of four to five days with no special curing. The 2-inch average slump concrete produced an average 7-day strength of 6,345 psi.

END

Readers who would like to have additional information on the subject discussed in the foregoing article may request it by filling out one of the reader service cards in this issue.

FRANK LLOYD WRIGHT'S GUGGENHEIM MUSEUM

**He adds new dimensions to the use of poured
concrete in building construction**

BY GEORGE N. COHEN*

In our cover photograph Architect Frank Lloyd Wright and the author are seen inspecting one of the four-foot diameter reinforced concrete columns in the Solomon R. Guggenheim Museum.



ON FIFTH AVENUE, between 88th and 89th Streets in New York City, one of the most unusual concrete buildings ever constructed — the Solomon R. Guggenheim Museum — is nearing completion.

Featuring a spiral ramp making six turns at an approximate grade of 3 percent, stiffened by exterior webs at 30-degree intervals, and an inner court covered by a glass dome, this structure represents the great architect's conception of a natural facility for viewing modern art in a modern setting.

Reinforced concrete was used throughout, with lightweight "Lelite" aggregate for the superstructure. All concrete was designed for 3,500 psi and a plasticizing admixture was used throughout the project. Slump was kept at 3 to 4 inches. Expansion joints were carefully omitted. Control of concrete for uniform strength, the inherent shape of the structure, the arrangement of reinforcing, and the planned extent and location of pour sections, all contributed to the elimination of cracking, a quality so essential for architectural concrete.


*Mr. Cohen is president of Euclid Contracting Company, New York City, general contractor for the Guggenheim Museum.

The entire project actually incorporates three types of concrete. Lightweight expanded-shale concrete is used in the ramp and floors, while stone concrete (also of 3,500 psi strength) has been used for the interior walls to assure a smooth finish. The outer walls were formed by spraying 5 inches of concrete against curved plywood forms, this work being handled from the inside of the structure.

The foundation presented no unusual problems. Soft rock was conveniently encountered at levels not too far below the basement, and footings were carried to it. Old foundations were encountered and removed. These were massive masonry walls and piers deeply imbedded in virgin soil by the old master builders of the past century, who either had little conception of the strength of their materials, or were blissfully unconcerned with costs.

In view of the fact that the concrete structure was mostly exposed, both exterior and interior, and also in view of the fact that the shapes of the component parts were so unusual, great care had to be exercised in the design and erection of the formwork. Detailed dimensional drawings were prepared and used extensively. Isometrics and large scale templates were made to

CONCRETE CONSTRUCTION




The Solomon R. Guggenheim Museum as it will look when completed late this year. As nearly all-concrete as building construction can be, it abounds in some of the most daring and intricate poured-in-place cast concrete work ever attempted in this country.


This photograph, taken from an upper story of an adjoining building, shows one of the upper levels of the ramp in the Museum wing in the foreground, and in the background at the left the roof of the 4-story circular administration wing.

elaborate and translate the intent of the architecture. Depending upon the radii and the shapes, varying thickness and types of plywood, prestwood and metal molds were used. Great care had to be taken in order to provide accurate and uniformly true lines, arises, and surfaces. An intricate mold in concrete is accentuated by good workmanship—and this was the premise throughout.

The structural design features rigid slabs with spans up to 60 feet and cantilevers up to 25 feet, some with highly concentrated end loading. The main ramp cantilevers 14 feet 6 inches to the inner court from a 13-inch deep rigid exterior beam of varying widths. Since the greater widths occur at the higher levels, the overall width of the ramp increases as it spirals upward.

The inside edge of the spiral ramp, which carries a 3-foot high plaster parapet, turns on a smaller and smaller radius as it rises upward. Similarly the outside edge which carries the gunite curtain wall turns on a greater and greater radius as it rises upward. The relationship between these constantly changing radii and the gradually rising plane of the ramp is so arranged that at any point in the height of the structure a horizontal plane will always





This view from street level shows the maze of scaffolding enclosing the circular Museum wing. The ramp makes six turns in all as it spirals up from the main floor to the top level.

Here a portion of the ramp is shown with the reinforcing steel in place ready for pouring operations to begin. The structural slab of the ramp tapers in thickness from 13½ inches to 4½ inches. It is topped with a 2-inch terrazzo finish.




intersect a true circle. This is the result of a basic pattern of shapes. It is a conception of a large cone (whose apex is theoretically some 180 feet below datum zero) into which is fitted an inverted smaller cone whose apex is theoretically some 270 feet above datum zero.

To lay out this complex structure would ordinarily be extremely difficult, but the work was simplified by an overall grid system of 8-foot units. All lines, radial points and axes tied into this grid system in a precise pattern which gave the component parts of the structure an orderly natural scheme. All working points were tied by coordinates into the grid system, and for checking purposes the center point of the structure was physically carried up as the job progressed. The shop drawings and layout plans were accordingly superimposed upon this grid system.

Intricate and beautifully formed concrete members, becoming planting areas, fountains, utility cores, pipe spaces, oversize circular columns, arches and cantilevered balconies, blend smoothly into the whole structure as though they truly belong to it, which they do. Such is the genius of the great architect whose design is so clearly and naturally portrayed.

The outer walls generally consist of 5 inches of gunite shot from the inside against a carefully erected plywood form bent to the shape required—both circular and sloping. These gunite walls are rigidly connected to the ramp slab and web. They are rein-



forced with 2 layers of 2 by 2 mesh, plus 2 layers of No. 3 bars at 12-inch centers horizontally, plus 2 layers of No. 4 bars vertically, plus top and bottom continuous No. 4 bars—all secured to a framework of 1½-inch tees which are in turn tied into the structure. The inside surfaces of these walls are furred, lathed and plastered. The outside surfaces are smoothed after the forms are removed, but while the gunite is still green.


The facia of one of the roof parapets had been designed in sheet copper stamped to a geometric pattern. Due to the difficulty of stamping and erection, these sections were precast in concrete to the required pattern in faceted slabs. These slabs were then treated and sprayed with molten copper in the shop. They were then sent to the job, erected on centering and concrete poured to hold them in position.

The building is heated by means of radiant tubes located under the terrazzo finish of all floors. A 250-ton absorption machine utilizes steam heat and lithium bromide in a chemical process for the air conditioning system.

Although he has designed some 700 buildings in all, this is the first major project Frank Lloyd Wright has built in New York City. His representative on the job is William H. Short. The general contractor for the entire structure is Euclid Contracting Corporation of New York City. The work is being done under the direction of George N. Cohen, assisted by Joseph Neukrug. Charles W. Spero is job superintendent and project manager. END

The view above shows some of the intricate precision formwork at the windows of the basement-level lecture room. Since most of the concrete in the structure is exposed, elaborate care was exercised to achieve the utmost accuracy and the finest possible surface texture.

Cross sectional view of the Museum wing showing how the spiral ramp is employed to give access to the art displays along the outer wall at the right. At the first floor level the ramp has an inner radius of 32 feet and an outer radius of 48 feet, while at the fifth level the inner radius has decreased to 25 feet and the outer radius has increased to 57 feet. Starting at the main-gallery level, the ramp rises 11 feet with each complete revolution.



Symons Forms Ganged for Anchor Walls




ASSEMBLY COST ONLY 5c A SQ. FT.

Modern forming methods answer the need of the jet age on the new TWA hangar at New York's International Airport. Symons 4 x 6 and 4 x 8 foot panels ganged in units 34 feet wide by 27½ feet were used for forming the 28 anchorage walls which straddle the full 80 foot roof width of the main building.

By using this method of forming, the contractor, Grove, Shepherd, Wilson & Kruege, Inc., poured the hangar in place at the cost of a precast structure. Panels were assembled on the ground at a cost of only 5¢ a square foot. It took about 15 minutes for a crane to tilt a gang form off the slab and inch it into place on the roof. 15,000 square feet of Symons wide panel forms were used in this gang forming operation. Symons wide panel forms have steel struts and 2 x 4 cross members to strengthen the panel and minimize deflection during pouring. Tie holes in the steel struts allow insertion and removal of special ties. Any strength tie may be used, including Williams removable end ties. Individual panels are built in 6' and 8' lengths and 30", 36" and 48" widths.

Project Manager, A. R. Maxwell, working closely with the local Symons forming engineer, devised this fast, efficient method of forming. This type service is available to all contractors, as well as the preparation from your plans, complete form layouts, bill of materials and recommendations for the best and least costly method of forming—there's no charge or obligation.

Symons Forms Shores and Column Clamps may be rented with purchase option—rentals to apply on purchase price. For more information on Symons products and service send for our FREE catalog.



Typical anchor wall elevation showing Symons wide panel forms ganged into units 34 feet wide by 27½ feet high. There are a total of 28 cable anchor walls on roof of the main building.

Symons
SYMONS CLAMP & MFG. CO.

4271 Diversey Avenue Dept. C-8
Chicago 39, Illinois

Warehouses located in California, Kansas,
Minnesota, Pennsylvania and Texas.

Sales offices and agents in principal cities.

CONCRETE CONSTRUCTION




Photo courtesy of Blaw-Knox Company

The bent in the foreground of this view shows how the completed concrete columns are being utilized to support the weight of the formwork and the concrete as it is placed. The column forms are in place for pouring one of the lifts and the strut form is also in position below. Several finished pier bents are visible beyond the one under construction.

COMPLETED WORK CARRIES WEIGHT OF FORMS AND CONCRETE

A NEW IDEA IN STEEL FORM DESIGN now makes it possible to support over 300 tons of form and concrete high in the air without falsework. The load is carried on completed work.

These special forms are now being used by Johnson-Kiewit, joint venturers on the \$6-million sub-structure contract for the new 4-lane high level bridge being constructed for the Berkshire section of the New York State Thruway.

The sub-structure consists of 42 pairs of circular concrete piers varying in diameter from 5 to 14½ feet. The pier bents are spaced 97 feet 6 inches apart with the exception of three central spans of 420, 600, and 420 feet which cross the river. Each pier, excepting five short ones near each end, is tied with an intermediate concrete strut at the 60-foot level and a pier cap.

To form the columns, which range

Close-up showing one of the 20-foot lengths of column form in place after the concrete has been poured. Note that the base of the form rests on bolts which have been cast right into the column on the previous pour. The form is insulated to permit the contractor to work right on through the coldest winter weather.



in height to 135 feet, the contractor is using 320 lineal feet of 8-foot diameter steel column forms. These forms are fabricated in 5-foot lengths by 180-degree segments. Pouring 20-foot lifts, the contractor has sufficient forms to keep four sets of 8-foot piers working all the time. There are 40 lineal feet of 14½-foot circular forms for river piers and 20 feet of 14-foot forms for anchor piers. With some 7,000 lineal feet of columns to pour, the column "cans" will receive nearly 20 re-uses.

Working up from the foundation, the contractor uses a crane to handle his column form in full circular sections which consist of two 180-degree panels. A special truss, made by the contractor, is placed between piers to keep the distance uniform and the work plumb. Once the bolts which connect the column form halves are tightened, no further support is required.

As pours are completed the joint bolts are loosened and 20-foot lengths of the form are moved up. The base of the form rests on bolts which have been cast into the column on the previous pour.

In the two units which form a third of the column's surface, bearing blocks are integral parts of the form. The two blocks protrude 3 inches into the concrete when the pour is made. Anchor bolts 1½ inches in diameter are inserted through the blocks before the pour for additional support. The bearing blocks, which are left in place with the form panels to which they are attached when the strut pour is made, transmit the vertical shear to the columns. The anchor bolts absorb the resulting horizontal thrust.


With this arrangement on the 8-foot diameter columns the weight of the 12½-ton strut form and 65 cubic yards of concrete (a total of some 131 tons) is supported. Similarly, the 20½-ton pier cap forms and 118 cubic yards of concrete (or some 239 tons) are supported.

END

Readers who would like to have additional information on the subject discussed in the foregoing article may request it by filling out one of the reader service cards in this issue.

Techniques and data . . .

for making
and testing
all types of
CONCRETE



Best ways of placing and curing—improved methods of testing and inspection—important facts on the properties of component materials—these and other matters are treated in a new book which offers you a *wealth of practical information* on every phase of concrete work.

COMPOSITION AND PROPERTIES OF CONCRETE

By G. E. Troxell and H. E. Davis
Professors of Civil Engrg., U. of Cal.

434 pages, 6 x 9, 161 illustrations, \$7.75

EACH OF THE ESSENTIAL FACTORS in making and using concrete successfully is explained in this book. It thoroughly covers materials and operations in a way that helps you insure top economy and efficiency. Properties of component materials, including cements, aggregates, admixtures, and water, are analyzed. Proved methods of proportioning, batching, mixing, placing, and curing are described in detail. The book also presents the best accepted techniques for inspecting and testing concrete—enabling you to control quality within well-defined limits.

Strength of hardened concrete . . . permeability . . . durability . . . shrinkage and expansion due to moisture changes . . . creep . . . elastic, thermal, and other properties . . . you are shown their significance and how they are affected by the many steps in fabricating the final product.

DETAILED METHODS OF


- measuring entrained air in fresh concrete
- handling and storing aggregates
- using accelerators and antifreeze agents
- determining composition of fresh concrete
- checking weighing equipment for batching
- conveying concrete pneumatically
- and scores of others

Order now from

CONCRETE CONSTRUCTION
139 N. Clark St. Chicago 2, Ill.

PAYMENT MUST ACCOMPANY ORDER

CONCRETE CONSTRUCTION



HOW TO SAVE 30%+

on concrete forms and finishing costs

SAVE ON FORMING AND STRIPPING. Forms go up faster and easier with handy 4' x 8' overlaid panels. Smooth, hard surface speeds stripping time.

SAVE ON RE-USE. The overlaid surface is resistant to harsh aggregates, can be used over and over, eliminates rebuilding forms during job.

SAVE ON SMOOTH, PAINTABLE SURFACES. The hard, glossy form assures smoothest possible concrete, reduces finishing time and labor to a minimum, eliminates expensive plastering. Specify "Simpson High Density Concrete Form."

Write for free sample and additional information.

Simpson High Density Overlay Plywood (Concrete Form) is an exterior-grade fir plywood with a resin impregnated fiber (KIMPREG) applied to both faces under heat and pressure. Available through your distributor.



RELY ON



Simpson Logging Company
Sales Office, Plywood and Door Products
2301 N. Columbia Blvd.,
Portland 17, Oregon
Regional Offices in New York, Cleveland,
Chicago, Denver, Minneapolis, Memphis,
Dallas, Los Angeles, Portland, Seattle.

PD-82B

OVER
20,000,000

**SQ. FT. OF CONCRETE FLOORING
ALREADY FORMED WITH**

 **Spanall**®
HORIZONTAL SHORING



WHY?

Because Spanall proved it in less than 2 years: savings up to **40%** on all beam and slab formwork. From coast to coast, in Canada and in Latin America, contractors choose Spanall because it's the better, quicker, easier and less expensive way to do the job.


No wonder SPANALL is so popular for beam, slab and suspended formwork! It's so easily installed . . . with built-in camber . . . with ample load-bearing safety factor . . . with clear, open work spaces in areas below the formwork—eliminating forever the forests of cumbersome, costly vertical shoring.

Stripping, too, is fast and easy; SPANALL sections are quickly moved and positioned for successive formwork . . . or telescoped and stored with space-saving economy.

Expert, on-the-job engineering service is always at your command—from your local SPANALL distributor, or from the home office. For complete information write directly to Department N.



SPANALL HORIZONTAL SHORING efficient time-saver on floor and deck concrete formwork: flat slab . . . beam and slab . . . structural steel . . . metal pan . . . drop head . . . filter block.



Repeated use of SPANALL HORIZONTAL SHORING, assembled to desired span lengths, speeds formwork construction on Carquinez Bridge along new California State H'way system.



SPANALL OF THE AMERICAS, INC.

Home Office: 787 United Nations Plaza, New York 17, New York, U. S. A.

Offices and Distributors in Principal Cities
throughout United States, Canada and Latin America

MR. BUILDER: Now you can
"STOP PASSING THE BUCK"
 with the
NEW kewanee
"BUCK WINDOW"
 COMBINATION STEEL BASEMENT
 WINDOW WITH... INTEGRAL POURING
 FORM
 (BUILT-IN BUCK)




KEWANEE'S FINEST WINDOW

PAT. PENDING

WINDOW WELL ATTACHMENT

Save Dollars in "Installed Costs!"

- **ONE MAN Rapid INSTALLATION** — lightweight, easily positioned and nailed to concrete forms.
- **STOP LABOR WASTE** — no steel or wood bucks to strip, clean and haul.
- Properly installed, no lintels needed.
- End expensive call-backs, finishing problems.
- 3 standard window sizes in 3 full wall thicknesses 8", 9" and 10". Special wall thicknesses on request.
- **CORRUGATED WINDOW WELL (OPTIONAL)** — Specially designed to fit BUCK WINDOW.
- **INSTALL IN SECONDS** — All you do is back off screws in face of window frame... position corrugated well... tighten screws. No need for studs, concrete nails, lag bolts, etc. Screw driver does the job.
- 6 standard corrugated window well heights, 12" through 36" in both round and straight types.



OTHER KEWANEE BASEMENT WINDOWS
 Standard • Master • Aluminum
 (All available in both putty and puttyless types.)
 Packaged Window Putty Glazed.

KEWANEE STEEL DOOR FRAMES
 3 Types for both plaster and dry wall construction.
KEWANEE STEEL BUCKS

See your dealer today... or write to

KEWANEE MANUFACTURING COMPANY	
358 AVERY STREET	KEWANEE, ILLINOIS
NAME _____	
FIRM _____	
ADDRESS _____	
CITY _____	STATE _____


equipment and tools

For more information mail cards facing page 16.



Perimeter Insulation


Scorbord is a black smooth-surfaced board of expanded polystyrene 1 inch thick, 2 feet wide and 8 feet long. Three striations cut the length of each board at the 3-, 12-, and 20-inch marks across its width permit the installer to snap off the widths desired, thus reducing work time up to 50 percent. Structural strength permits pouring of concrete slabs directly upon it. It is lightweight, waterproof, rot-proof, chemical resistant and has no food value for rodents or insects. **Dow Chemical Company, Midland, Michigan.**



Power Buggy

A 10-cubic foot capacity power buggy allows the operator either to walk behind or ride on a fold-down platform. It is a compact, lightweight model designed to travel over narrow runways, into elevators and through doorways as narrow as 31 inches. A positive-control dumping mechanism permits accurate placement of concrete. Speeds up to 5 mph are attainable. It is powered by a Wisconsin engine, and has front-wheel chain drive, automatic clutch and forward and reverse drive. **Whiteman Manufacturing Company, 13020 Pierce Street, Pacoima, California.**

View of a tensile bond specimen under test at the National Bureau of Standards. Indications are that the cracks that occur in concrete are narrower near the surface of the steel reinforcing bar than at outside surface of the concrete, thus exposing less steel to atmospheric corrosion than was previously believed to be the case.



WIDTH OF CRACKS IN REINFORCED CONCRETE

IN DESIGNING a reinforced concrete structure, the engineer takes into account the fact that cracks will eventually develop in the structure. These cracks expose the reinforcing bars to the atmosphere with consequent corrosion which can weaken the entire structure. Recent evidence* uncovered at the National Bureau of Standards, however, indicates that these cracks are narrower near the surface of the reinforcing bar than at the outside concrete surface, thus exposing less of the bar to corrosion than was heretofore believed. These measurements, made by D. Watstein and R. G. Mathey of the Bureau's structural engineering laboratory, are expected to be of value to the structural design engineer in making better use of existing design data, with consequent savings in materials.

Conventionally reinforced concrete normally develops numerous fine cracks when the tensile strains caused by loads, drying shrinkage, and thermal changes combine to exceed the

limit of extensibility of concrete. Only through careful design and proper selection of well-designed deformed reinforcing bars can the designer limit the width of these cracks to safeguard the steel bars against corrosion. It had been previously believed that the cracks were, on the average, nearly uniform in width from the surface of the concrete to the surface of the bars, and this assumption was followed in designing structures. Since there was indirect evidence that this assumption was not entirely true, the Bureau undertook a more detailed study of the variation of width of cracks.

The crack width measurements were made on tensile bond specimens designed to simulate a portion of the tensile zone of a reinforced concrete beam between two successive cracks. Each specimen was essentially a prism of concrete 8 inches long with a reinforcing bar embedded along the longitudinal axis. A tensile force was applied to the ends of the bar. The extension of the embedded portion of the bar, the over-all extension of the concrete prism at points $\frac{1}{8}$ inch from the surface of the bar, and the over-all change in length of the exterior surface of the prism were determined.

Since the length of the exterior surface of concrete remained substantially constant during the test, the over-all extension of the embedded bar was taken as the width of crack measured at the surface of concrete. The difference between the extension of the embedded bar and that of the concrete adjacent to the bar was assumed to give the width of crack at the surface of the bar.

The ratio of the width of crack at the surface of the bar to that at the exterior surface of concrete has been plotted against the applied stress, to provide the engineer with the necessary design information. This reduction of crack width in the vicinity of the surface of reinforcing steel was observed only for deformed bars; no measurable reduction of crack width was observed with smooth round bars.


END

Readers who would like to have additional information on the subject discussed in the foregoing article may request it by filling out one of the reader service cards in this issue.

*D. Watstein and R. G. Mathey, Evaluation of width of cracks in concrete at the surface of reinforcing steel by means of tensile bond specimens, RILEM Symposium on Bond and Crack Formation in Reinforced Concrete, Stockholm, 1957.

A College Study Reveals Some New

Tilt-Up Techniques for Small Panels



After determining the building size required, lay out the structure at the desired location. If a floor is needed, pour the slab. Footings should be cast where wall panels are to butt if a dirt floor is to be used. Make sure sub-soil conditions are stable enough to preclude any settling.

ALTHOUGH LARGE CONSTRUCTION PROJECTS usually get the lion's share of publicity, small- and medium-sized jobs constitute the bread-and-butter business of most concrete contractors. Recognizing this truism, the Texas Agricultural Experiment Station, in conjunction with the Portland Cement Association, initiated a study to develop economical methods of constructing relatively small buildings. The results were shown at a recent demonstration meeting held at Texas A&M College.

Basically the work had been aimed at devising a simplified tilt-up construction procedure for which unskilled labor could be used on farm projects. No attempt was made to circumvent contractors; care was taken to point out that a qualified contractor should be employed to supervise the construction operations.

The most important step in reducing costs and equipment requirements was the development of a simplified lifting technique. Initially wall panel

sizes were examined with an eye to arriving at a versatile and practical module that would be easy to lift. It was found that 8-foot or 10-foot square wall panels would be the right size for more than two-thirds of the building plans for farms.

Accordingly, two buildings (20 by 40 feet and 20 by 60 feet) were built for experimental work. Panels were poured on the floor slab or, lacking this, on a bed of sand. A polyethylene sheet was used to prevent bonding of the panel and the casting bed. Ribbed panels were cast at first but some difficulty was encountered when the work was done by relatively inexperienced workmen. Solid panels were found to be easier to cast and light enough to be handled by common farm machinery. Door and window bucks, together with inserts for the lifting frame, were simply inserted in the forms and secured in place. Panels were cured for three days before being tilted.

At first, panels were tilted with an

Readers who would like to have additional information on tilt-up construction may request it by filling out one of the reader service cards in this issue.


Build the wall panel forms. They should be adjacent to their final position, if possible, to eliminate any difficulties in moving them horizontally. Provide adequate reinforcing to prevent cracking during the stress of lifting; and securely position inserts and window and door bucks.




Carefully pour the concrete making sure that inserts, bucks and steel are not displaced. A polyethylene sheet between the panel and the floor slab or sand bed will prevent bonding between the two.



Inserts in the panels should be provided to attach the lifting rig. The device pictured proved to work well. It is a pyramidal frame built of 2-inch pipe with its point of hitch 10 feet above the panel. This frame distributes the lifting stresses evenly throughout the concrete.



The drawing below shows some of the details of the tilting frame used for erecting concrete walls panels in the study conducted at the Texas Agricultural Experiment Station. A frame constructed in this manner provides enough leverage for tilting panels up to 10 by 10 feet.



A-frame on a winch truck. Panel damage and handling problems were considerable. After some experimentation a 2-inch pipe pyramidal frame, with the point of hitch 10 feet above the panel face, was found to work well. Two 2-inch diameter roller assemblies were found to be adequate for moving panels horizontally when the panels weigh 4,000 pounds or less. Whenever possible, however, it is advisable to cast the panels so that they can be tilted directly into place.

Once in place, the panels were braced and an H-shaped cast-in-place column connection was poured between adjacent panels. Any kind of roof can be erected on the resulting structure.

During the construction of these buildings the following observations were made. The largest tractor available should be used to assure a smooth tilting operation. Uneven, jerky tilting results in damaged panels. Concrete should contain six sacks of cement per cubic yard for best results. At least 10-inch square footings should be provided under each panel end. Panels of 4-inch thickness need at least four $\frac{3}{8}$ -in. reinforcing bars for vertical tension, two in compression, and in addition a horizontal bar in tension at the bottom and the top of the panel. Large panels and those with openings need more steel. Every piece of steel should span the entire panel. Leave one side edge of every panel unbonded with the column connection to allow for thermal movement.


These experimental buildings demonstrated the considerable cost savings possible with tilt-up construction. Texas A & M has accumulated the following cost data for a 60-foot long, 8-foot side wall animal shelter with an open front and an earth floor; cost per square foot for a 20-foot wide unit, \$1.18 in pole frame, \$1.66 in steel, and \$1.24 in tilt-up; cost per square foot for a 30-foot wide unit, \$1.00 in pole frame, \$1.58 in steel, and \$1.07 in tilt-up.

Cost of the 20- by 40-foot machinery shed with dirt floor (figuring labor at \$1.50 per hour) was only \$854, and \$334 of this amount was for the roof. As one Oklahoma contractor put it, "This will be a real boon to our farm customers. When you've lost your buildings to fire, you're easy to sell on concrete. And this is the easiest way to handle concrete I've ever seen."

END




Here the 2-inch pipe pyramidal frame is attached to the panel at all four points, and the actual job of tilting is about to begin. The polyethylene film on which the concrete is placed provides an excellent bond breaker with the subgrade.



A strong cable is then attached to the rig's hitch point and a tractor. The most powerful tractor available should be used to assure a smooth lifting operation. Jerky, uneven lifting results in cracked panels. Once in place, panels should be braced.


BELOW: The 20- by 40-foot machinery shed after completion.



equipment tools materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards located between pages 20 and 21 in this issue.



Waterstop

A polyvinyl plastic device is installed by attaching to the inside of the temporary terminal board by driving nails partway in, leaving the heads projecting enough to become embedded in the pour. The flexible, tough plastic allows for expansion and contraction and is resistant to temperature changes, acids and aging. It saves time and money in the construction of sewage treatment plants, tanks, basements, tunnels, water reservoirs, swimming pools, and dams. **Water Seals, Inc., 9 South Clinton Street, Chicago 6, Illinois.**

Tractor-Loader

A new 4-wheel drive, rear-wheel steer tractor-loader in the 1¾-cubic yard class is powered by a Case industrial engine, has 11,000 pounds breakout force at ground level, and 5500-pound lift capacity. Outstanding advancements in operation and safety include rigid lift-arms pivoted forward of the operator's seat, improved stability, power shift and steer, Torqmatic drive, speeds to 21 mph in both forward and reverse, with controls and color-coded instruments designed for easier, faster operation. **J. I. Case Company, Racine, Wisconsin.**




Perimeter Insulation

Gold Bond Thermo-Bloc perimeter insulation applied to the bottom and edges of concrete slab or to the inside of foundation walls effectively reduces heat transfer at these points to a minimum. This permanent heat barrier saves the builder about 25 percent of material cost by eliminating the need for paper or asphaltic coatings. It is non-capillary and will not absorb wet concrete and solidify. It is available in 4-foot lengths of various widths and is easily cut. **National Gypsum Company, Buffalo 2, New York.**

Bar Bender

Modern big project construction requires speed, strength and ruggedness in bending apparatus. This heavy duty bending machine, a simplified, flush-table type, is designed to fill this requirement. It will make any kind of bend, except radial bends, in reinforcing steel of any size up to No. 9 bar. Design simplicity promotes easier operation and reduced maintenance. It is operated by a 20 HP motor, weighs 7,400 pounds and measures 6 by 6½ feet, with 30-inch table height. **Monarch Forge & Machine Works, Inc., 2130 N. W. York Street, Portland, Oregon.**



YOU ARE MONEY AHEAD WITH Simplex

World's Fastest Method of Concrete Forming

Set Faster



Because Simplex panels are light in weight, and a minimum of handling is required, they set faster with less fatigue. Inner and outer panels can be dropped in approximate location and set-up simultaneously. This eliminates extra handling and backtracking. Forms go up a foot a minute. Walls for a 120' foundation can be set up in 1½ hours using only 3 men.

Pour Faster



With line-up rails in place (they slip over tops of panels to insure accurate alignment) and with grades set, you can pour an 8' wall in a 120' foundation in less than 2 hours. Pour at one corner or four corners simultaneously.

Strip Faster



Stripping a 120' foundation requires less than 3 man hours. After quick break-off of Simplex tie-wires, panels are unlocked easily, then swiftly removed. Workmen appreciate Simplex light weight (an 8' panel weighs only 65 pounds) as panels can be moved speedily with less effort.

Accurate Work



Rugged 1½" panels are accurately cut and drilled, with precision-made hardware firmly bolted in place. The combination of the metal backing bar and patented Simplex locking lever insures positive alignment . . . minimizes seam marks . . . gives a clean, professional job you can show with pride.

Move Faster



Yes, you move faster because a complete set of forms—including all panels, fillers, corners, scaffold brackets, and line-up rail can be stacked on one 12-foot bed truck. There's no down-time looking for loose hardware. Simplex Forms are designed to speed your work and get you to your next job in jig time.

GET ALL THE PROFIT MAKING FACTS:

Concrete Exposition-Booths 211-212, Chicago Coliseum, Feb. 24, 25, 26

OR WRITE FOR BULLETIN TODAY

SIMPLEX FORMS SYSTEM, INC.
5603 Industrial Ave., Rockford (Loves Park) Illinois

Distribution Points

St. Louis, Mo. — Salt Lake City, Utah — San Leandro, Cal. — Denver, Colo.

Simplex
FOOT-A-MINUTE
forms



Fly Ash Gives Plenty of "Fine Fines" for Quick, Easy Placing, Smooth Finishing


The Modern Mix Employs Cement and Fly Ash for Best Results

Desired: a concrete mix that is easy to place and fills the forms completely — but does NOT require more water than usual to accomplish this.

Fly Ash with Portland Cement does it, yielding a concrete of superior quality, better in several ways than straight cement concrete, quicker and easier to finish.

Smooth Surfaces, Sharp Edges

Fly Ash is a fine powder from pulverized-coal-burning power plants — largely spherical, smooth, glassy particles of silica and alumina, as fine as or finer than cement.



In addition to its chemical actions improving the concrete, Fly Ash increases the fine fines in the mix and literally gives it "ball bearings" that speed placing and finishing. In the highly magnified views above note the rough, irregular particles of cement (right) contrasted with the smooth balls of Fly Ash (left). They show why Fly Ash in the mix makes it "roll" into place better.

WALTER N. HANDY CO., INC.
910 Custer Ave., Evanston, Ill.

McNEIL BROTHERS, INC.
P.O. Box 4015, Bridgeport 7, Conn.



Fly Ash in the mix greatly reduces "honeycomb" effect, saves a lot of going back to the job to fix that condition. It makes a less porous concrete, less subject to cracking, more watertight.

Speeds the Building

Tests show one-day strengths ample for stripping where desirable. Strengths at 28 days and longer are often greater than those of straight cement concrete.

For Information—Help

Send for information on correct proportioning of Fly Ash mixes. Your established ready-mix concrete man can design the ideal mix for your work; can predict the 28-day strength to expect.

Each company below has staff engineers to assist you with data and technical help. Call or write:


DETROIT EDISON COMPANY
2000 Second Ave., Detroit 26, Mich.

CHICAGO FLY ASH COMPANY
228 N. La Salle St., Chicago 1, Ill.

equipment and tools


Horizontal Shoring

Spanall all-steel horizontal shoring is being used in forming floors in the world's tallest reinforced concrete building, University City Institute in Caracas, Venezuela. This shoring for beam and slab concrete deck and floor forms is quickly installed and stripped. It provides free work space below formwork. **Spanall of the Americas, Inc., 787 United Nations Plaza, New York 17, New York.**



Prestressed Reservoir

Prestressing, and the use of rubber seals for joints, are among the noteworthy features of a 3-million gallon concrete reservoir recently completed near Los Angeles. Individual wall sections were first poured on top of a ring of rubber stripping, then pulled together and prestressed with over 120 miles of high-tensile steel wire. **The Gates Rubber Company, 999 South Broadway, Denver 17, Colorado.**




CONCRETE CONSTRUCTION



*products
for
concrete
construction*

See us at Booth 155-156
1958 Concrete Exposition
Chicago Coliseum
February 24, 25, 26

**WRITE FOR THE NEW
FULL LINE CATALOG
TODAY**



FORM CLAMPS
SNAP TIES
TWISTIES
SPIROLOCKS
BAND CLAMPS
BEAM CLAMPS
BAND IRON
SOFFIT SPACERS
CONE NUTS
INSERTS
ANCHOR SLOT
ANCHORS
CONSTRUCTION
STAKES
REINFORCING
BAR SUPPORTS
DOWEL BASKETS
STAKE PINS
UNI-FORM PANELS

UNIVERSAL FORM CLAMP CO.
1238 N. KOSTNER • CHICAGO 51, ILLINOIS

CONCRETE FORM SPECIALISTS SINCE 1912

**BRANCH OFFICES
AND WAREHOUSES**

SAN LEANDRO, CAL.
2051-9 Williams Street

HOUSTON, TEX.
2314 Preston Ave.

BALTIMORE, MD.
1020 N. Krossman St.

LOS ANGELES, CAL.
13210 S. Figueroa St.

CLEVELAND, OHIO
24801 Lakeland Blvd.

ATLANTA, GEORGIA
1401 Howell Mill Rd., N.W.


Universal Form Clamp Co. 1238 N. Kostner, Chicago 51, Ill.

MARCH 1958

equipment tools materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards located between pages 20 and 21 in this issue.




Concrete Form Stake Package

A combination of items revolving around a solid round steel stake, with nail holes in a spiral arrangement, offers the concrete contractor an economical means of staking and bracing low forming. The combination of the steel stake, steel spreader bar, steel brace and form joiner plate permits form setting 5 to 10 times faster than with wood, there is no material clean-up after stripping, and all items can be used repeatedly with continuing savings in material and labor. **Dee Concrete Products Co., 670 N. Michigan Avenue, Chicago 11, Ill.**

Car Unloader

This car unloader can be used as an over-the-rail type unloader or it can be used in a standard pit, making it extremely adaptable to ready-mix operations for unloading bulk materials onto stock-piling conveyors. It is powered with either electric motor or gasoline engine. A tow hitch is provided. The combination belt and chain provide positive, non-slip operation at capacities up to 185 tons per hour. Overall dimensions are 20 feet 10½ inches by 33½ inches. **The Fairfield Engineering Company, Marion, Ohio.**



Mobile Construction Building

Ideal for field office, storage or temporary housing, tool shed or workshop, the Economy Mobile Construction Building is a rigid, factory-constructed, 7½ by 16-foot building designed to answer the contractor's demand for mobility from job to job. It is built of kiln-dried, tongue and groove lumber and mounted on a heavy-duty steel undercarriage. The trailer is equipped with tires and electric brakes controlled by the driver. The building is demountable from carriage or is available without undercarriage, complete with floor. **Economy Buildings, Inc., West Chicago, Illinois.**

Bond Prevention in Prestressing


The photograph shows application of Aeroflex plastic tubing for bond prevention over prestressing stands. Desired stress distribution pattern in beam is obtained by partial covering of several strand sections as shown in picture of partially completed beam. Aeroflex tubes can be seen at left end of beam. The tubing is easily applied over the strands by opening it and walking along the strand while pushing the opened tube against the wire. It is self-closing around the strand. **Anchor Plastics Company, 36-36 36th Street, Long Island City 6, New York.**



Don't worry about chilly nights when your concrete is treated with COLUMBIA CALCIUM CHLORIDE

CONCRETE PRODUCTS STILL SET FASTER

Make sure that Columbia Calcium Chloride is added to the mix you work with. It upgrades your product quality and cuts manufacturing costs. Pre-cast units, block, or pipe... Columbia Calcium Chloride reduces pre-steam holding time, steaming time, and the soaking period—yet curing is faster and more dependable. There's far less cracking during early handling. And your products have higher ultimate strength. You make earlier deliveries, save space on lower inventory. If your present mix *doesn't* contain Columbia Calcium Chloride, better order some right away.



Columbia Calcium Chloride works equally well in concrete made with normal, air entrained, or high early cements.

NO LAG IN READY MIX SET

Night temperatures lower than 70°F may make your customers turn up their collars, but the chill doesn't slow their jobs when you've treated your ready mix with Columbia Calcium Chloride. Treated concrete sets and strengthens much faster at lower temperatures than you'd ever expect, due to Columbia Calcium Chloride's unique action. Your customers' time-tight jobs benefit because this improved mix gives both initial and final set *three times as fast* as untreated ready mix. And how about this: early strength is 50% greater at 72 hours; ultimate strength tests higher, too. All this means earlier form removal, faster finishing, quicker job wind-up. Have *your* customers been getting these money-saving advantages?



You can add Columbia Calcium Chloride very economically, either at your plant or at customers' job sites.

WRITE TODAY FOR COMPLETE INFORMATION . . . PLEASE MENTION WHETHER INTERESTED IN READY MIX OR CONCRETE PRODUCTS

COLUMBIA-SOUTHERN CHEMICAL CORPORATION

SUBSIDIARY OF PITTSBURGH PLATE GLASS COMPANY
ONE GATEWAY CENTER · PITTSBURGH 22 · PENNSYLVANIA




DISTRICT OFFICES: Cincinnati • Charlotte • Chicago
Cleveland • Boston • New York • St. Louis • Minneapolis
New Orleans • Dallas • Houston • Pittsburgh • Philadelphia
San Francisco

IN CANADA: Standard Chemical Limited and its Commercial
Chemicals Division

equipment tools materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards located between pages 20 and 21 in this issue.



Trencher

The digging range of this compact, 6750-pound trencher is to 5-foot depths at 6- to 18-inch widths. Sixteen digging feeds, from 4.4 to 181 inches per minute, are available. There are four bucket line speeds, and four conveyor belt speeds. The conveyor is shiftable and reversible so spoil can be deposited on either side of the trench. Boom is telescopic for depth variation. The bucket line is self-cleaning. Traction and steering are handled through multiple disc friction clutches. **Parsons Company, Division of Koehring Company, Newton, Iowa.**

Bonding Agent

A new concrete ramp, 0 to 4 inches thick, was poured on old concrete floor over Zack-O-Mix, making a bond that withstands freezing and thawing, without chipping old concrete for feather edge. This material will repair wall cracks, moisture-proof basements, repair broken concrete, bond new floor topping to old floors, and coat surfaces against damage from acids or ice-removing chemicals. Tests indicate that this product halts capillary action, providing excellent moisture proofing. **Concrete Weld Company, Flint, Michigan.**




What Happens When You Can't Cross Property Lines to Form a Wall?

With only one-inch clearance to work in, here's how a problem was solved with Gates.

Problem: In forming the 14-foot-high foundation walls of this job, the contractor was not allowed to trespass on the adjoining property in any way, so all forming had to be done from the inside. Clearance between the foundation wall and the property line was one inch. In addition, exterior below-grade damp-proofing was specified by the architect.

Solution: Working with the local Gates representative, the contractor selected Gates Vertical Rod System for the job. Asphalt-coated corrugated metal sheets were used for the outside form panels and allowed to float. Conventional Gates methods were used for the inside of the wall. With the architect's approval, the coated metal sheets and 14-foot steel rods were left in place after the concrete was poured.

Results: The unique forming method cost no more than conventional Gates forming. Excellent results were obtained. This proven versatility of Gates Forming Systems can help you, too. Why not investigate?



Concrete forms—foundation wall of Harris Building, Oklahoma City, Oklahoma. Note corrugated metal sheets used for outside form panels.

Contractor: Commander Construction Co., Oklahoma City
Gates representative: Vernon L. Mock Co.



Gates & Sons, Inc.


80 So. Galapagos St.

Denver 23, Colorado

CCM-3/88

equipment tools and materials

Additional free information concerning these items may be obtained by mailing the reader service cards located between pages 20 and 21.




Vibratory Screed

A new double-action vibratory finishing screed vibrates, compacts and levels concrete through a high-frequency slapping action. A gasoline engine actuates a series of steel straps between two beams, delivering the slapping action on the surface of the slab to force out water and air rapidly so that final power trowelling can be started quickly. Available in 7-, 10-, 13- and 16-foot lengths. **Thor Power Tool Company, Prudential Plaza, Chicago 1, Illinois.**


Power Trowel

Four reversible float blades, adjustable and weighing only 150 pounds, are features of this easy-to-handle 42-inch power trowel. Blades stop rotating when the operator lets go of the handle. A stationary guard ring makes it possible to work up to walls. The engine can be started at full throttle. **Stow Manufacturing Company, 443 State Street, Binghamton, New York.**




Plank and Stairway Unit

A heavy-duty plank and packaged stairway unit, both designed for use with this manufacturer's sectional steel scaffolding, provide outside access to top additions to buildings and to high bridge construction. Planks are suited for use with rolling scaffolds, with stairways in stair towers, and as planking on scaffolds 3 or more frames long. **The Patent Scaffolding Company, Inc., Long Island City, New York.**




Bar Bender

Designed for the small contractor who must eliminate the expense of having prebent steel delivered, the Clyde Steel Bender shapes $\frac{1}{4}$ to $\frac{3}{4}$ -inch reinforcing steel to any form. It can be adjusted to produce a series of identical shapes. It can be carried in a car trunk and set up on job-site in 2 minutes. **Clyde Manufacturing Company, Inc., Bridgeway at Turney Street, Sausalito, California.**



LABYRINTH WATERSTOPS

A SOUND INVESTMENT FOR CONCRETE CONSTRUCTION



LABYRINTH AVAILABLE IN 2, 3 or 4 rib.

ON YOUR CONSTRUCTION:

1. Consider the investment in design, materials and labor (to mention a few).
2. Then consider how important safe, secure watertight concrete joints are.
3. Thorough watertightness can be secured by installing Labyrinth Waterstops—a dividend that makes the low initial cost of the product insignificant when compared to your total investment—and one that insures watertight concrete joints for years!

- Corrugated ribs grip concrete, insure an everlasting bond between joints.
- Finest polyvinyl plastic resists chemical action, aging, severe weather.
- Takes just seconds to nail to form... easy to cut and splice on location (prefabricated fittings available).
- There's a Water Seal product for every type of concrete work!

If your aim is to stop water seepage, stop it effectively with Water Seals' Waterstops!

"See Us in SWEET'S"

New Literature and Free Samples Sent on Request—Use Coupon Below

WATER SEALS, inc.

9 SOUTH CLINTON STREET, CHICAGO 6, ILL.

Made in Canada for J. E. Goodman Sales, Ltd.
Toronto, Ontario


WATER SEALS, INC. DEPT. 12
9 S. Clinton Street
Chicago 6, Illinois
Please send free sample and descriptive literature.

Name _____
Company _____
Address _____
City _____ Zone _____ State _____

equipment tools materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards located between pages 20 and 21 in this issue.



Stake Bar

Shown here is a steel stake bar, for use with the manufacturer's steel stake, which offers six positions for holding steel stakes apart in distances varying in multiples of two inches, from 16 to 24 inches. It is particularly adapted to low wall forming. Its flat surface with nail holes spaced 1-inch apart makes it easy to drive and nail firmly. A pull-out hole at the top permits fast removal with ordinary tools. Both bar and stake are reusable. **Symons Clamp and Manufacturing Company, 4249 West Diversey Avenue, Chicago 39, Illinois.**

Shoring

Only three parts comprise the Brainard Engineering Shoring System. One man can erect a 5-foot square tower quickly, and dismantling for use on the next job is simple. Screw jacks in each foot level the tubular steel frames and equalize the load, and ledger carriers inserted in top members allow the entire load to be borne by leg members. The notched sleeve in each leg permits swift slip-fit and locks one frame with another. A single 8-foot tower will support 28 tons. **Brainard Steel Division, Sharon Steel Corporation, 1313 Jefferson Street, Warren, Ohio.**



perfectly cured and hardened CONCRETE at a cost savings with DEMICON Cure Hard

One application of DEMICON Cure-Hard to freshly poured concrete surfaces will give you:

a perfect membrane that retains moisture and prevents cracking

a dust-free, chemical-resistant, hardened surface

a cost savings—material applied for less than 1¢ per square foot



McMILLAN FLOOR PRODUCTS CO.

2045 East Eight Mile Road Hazel Park, Michigan

For FREE Information write direct or use Reader Service Cards

FAST, low cost way to PERMANENTLY BOND new CONCRETE to old CONCRETE

WELD-CRETE®

What's your job? Concrete ramp, floor, highway, stucco wall, driveway, factory machine mounts? With WELD-CRETE, the amazing job-proved liquid bonding agent, you can permanently bond new concrete to old . . . or to any other sound surface . . . no matter how smooth! Just apply, let dry, and pour or trowel new concrete. Today specified by leading architects, contractors and builders for hundreds of large and small jobs . . . new construction, remodeling, repair. Get fact-packed literature from your WELD-CRETE dealer, or, write to Larsen Products Corp., Box 5756 S, Bethesda, Md.



Typical Weld-Crete Application: One of several Southern California High Schools where Weld-Crete was sprayed on new, smooth tilt-up wall to provide bond for sprayed on stucco application. Arch., H. L. Gogarty; Gen'l. Contr., J. C. Boespflug Contr. Co.; Plstg. Contr., A. D. Hoppe Co. Applicator: F. K. Pullen Co.

equipment tools and materials

Additional free information concerning these items may be obtained by mailing the reader service cards located between pages 20 and 21.

Masonry Drilling Guide

Tough masonry drilling jobs can be made easier by using Tilden Rotary Konkrete Kore drills with the Tilden masonry drill starting guide, which provides a means of precision locating and starting of hole with ease. Guide-holes provide for 1/4- through 1 1/4-inch diameter drills. **Tilden Tool Manufacturing Company, 209 Los Molinos, San Clemente, California.**

For Hoisting Concrete

Mason's mortar pal may be hoisted to pour concrete. Also it may be used to spread sand on finished concrete floors or gravel on roofs. The hoisting arm slips over a scaffold pin, and swings the load on the working area. It is installed and within a few minutes time relocated without the use of tools. **Mason's Pal Products, 509 Thornberry Drive, Evansville, Indiana.**

Mechanical Back-Up Alarm

Bullard Mechanical Vehicle Alarms are self contained and are constructed for use on trucks and fork lift trucks. Easily attached alarms operate independently of electrical circuits or speedometer. Hammers strike bell with the turn of the wheel, when vehicle is in reverse. Rubber cushions eliminate noise in the forward motion. **E. D. Bullard Company, 2680 Bridgeway, Sausalito, California.**

Tamper Attachment

The tamper attachment for the Bantam power cranes-excavators offers 80 to 100 percent compaction at a maximum penetration of 3 feet. Three full-lead passes at a given point in average ground will bring full compaction. The time and labor-saving advantages are apparent. The tamper is interchangeable with any of this manufacturer's other 9 attachments. **Schild Bantam Company, Waverly, Iowa.**

Midget Tractor

A new variation of the Mead Model R-9 midget tractor measures only 28 inches in width to the outer edges of the tracks—8 inches less than the standard model. This unit has three speeds forward and one reverse, and these are multiplied by the mechanical type of power steering, which has a dual range and neutral position. **Mead Specialties Company, SC-39, 4114 North Knox Avenue, Chicago 41, Illinois.**

Portable Hoisting Machine

The Buck Hoistower is a trailer-mounted unit which is self-erecting to heights of up to 45 feet. Additional tower sections can be added. The concrete bucket assembly allows concrete to be dumped at any height. Fourteen and 17 cubic foot buckets are available. Thirty-five cubic yards of concrete per hour can be poured. **Buck Equipment Corporation, 720 Anderson-Ferry Road, Cincinnati 38, Ohio.**

Metal Surveying Stake

A three-man crew used the Gradline Metal Stake in establishing exact line and grade for forms for five miles of concrete pavement in Washington, with savings in labor time. It can be driven mechanically or by hand, and eliminates cutting off wood stake at specified grade or calculating cut or fill from the top of a hub. **George E. Long Company, 16041 33rd Avenue, N. E., Seattle 55, Washington.**

Level

A new instrument shows exact level points at distances from a few feet to 150 feet. The device has a wide range of uses where the ordinary level is impractical and where it is difficult to establish sight points and recheck elevations with a transit or other instrument. **The Liqui-Level Company, Box 538 Redwood Drive, Felton, California.**

Dodson's Digest



A concrete idea for winter

Stopped by to see George Thomas the other afternoon. George is a contractor, who started in business about two months ago. His dad is one of my best friends.

"Hi, George! How's business?" I greeted him.

"I've got beginner's luck, Dod," he replied, dejectedly. "It's all bad!"

"Sometimes it only seems bad," I pointed out. "What's the trouble?"

"First off," he began, "I regard dad as a pretty good weather prophet—his rheumatism, you know. I landed a job for the streets and sidewalks in a 120-house subdivision. Dad had predicted warm weather, so I ordered the ready-mix and promised . . ."

"Wait a minute!" I interrupted, astonished. "Don't tell me your jobs are being scheduled according to your dad's rheumatism!"

"Oh, no!" he laughed. "I always check with the weather bureau, too. But," he said, getting serious, "this sudden cold snap is going to ruin me!"

"Well, weather doesn't have to be your enemy, George. Ever heard of Calcium Chloride?" I asked.

"Sure, Dod, but expenses are too high as it is," he insisted.

"Calcium Chloride will save you money!" I emphasized. "Ask your ready-mix supplier to add two pounds per bag of cement and you'll reduce your set time by two-thirds. Gives you higher early strength and increased workability. You'll be prepared for the cold and you can . . ."

"Maybe you're right, Dod," he broke in. "I just hadn't looked at it as a cost-cutter. I'll call the ready-mix plant tomorrow."

"Better call them right away," I warned him. "There's about six inches of snow due tonight."

"That's funny," George remarked. "I didn't read anything about it. Where'd you hear that?" he asked, puzzled.

"Farmer's Almanac," I grinned. "Very reliable."

—L. D. DODSON

P.S.—Don't gamble with concrete. Get the facts on what Wyandotte Calcium Chloride can do for you in our folder, "How To Make Better Concrete Products and Ready-Mix." For your free copy, just drop me a line. **Wyandotte Chemicals Corporation, Wyandotte, Michigan. Offices in principal cities.**

Wyandotte
CHEMICALS



MICHIGAN ALKALI DIVISION
HEADQUARTERS FOR CALCIUM CHLORIDE

NOW YOU CAN PAY-AS-YOU-BUILD



New, modern power equipment like Pumps, Power Trowels, Transit Levels — can be yours to USE while you pay for it out of the extra profits it helps you produce! And you get...

UP TO 12 MONTHS TO PAY!



FREE!

Full details on the new Pay-As-You-Build plan that lets you pay for new power equipment while it makes profits for you! Send for your free copy of this booklet! Write today!



TOOL COMPANY
1958 Walnut Street
Kansas City 8, Mo.

EFCO STEEL FORMS

for
concrete
construction



Consider these advantages:

- Easy to handle and assemble.
- Low original cost.
- Saving in time, material, money.
- Lifetime steel faces never need to be replaced.

Send coupon today for catalog

Economy Forms Corporation
Box 128, H. P. Station
Des Moines, Iowa

Please send catalog and address of nearest sales office (there are 21 coast-to-coast.)

Name

Firm name

Street address

City State

Index to Advertisers

Chicago Fly Ash Company.....	28
Columbia-Southern Chemical Corp.....	31
Concrete Transport Mixer Co.....	inside front cover
Dee Concrete Products Company.....	5
Detroit Edison Company.....	28
Economy Forms Corporation.....	36
Gar-Bro Manufacturing Company.....	2
Gates & Sons, Inc.....	32
Goldblatt Tool Company.....	36
Walter N. Handy Company.....	28
Kewanee Manufacturing Company.....	20
Larsen Products Corporation.....	34
The Master Builders Company.....	back cover
McMillan Floor Products Co.....	34
McNeil Brothers, Inc.....	8
Sika Chemical Corporation.....	3
Simplex Forms System, Inc.....	27
Simpson Logging Company.....	17
Solvay Process Division.....	7
Spanall of the Americas.....	18 and 19
Stow Manufacturing Company.....	4
Symons Clamp & Manufacturing Co.....	14
Syntron Company.....	6
Thor Power Tool Company.....	inside back cover
Truck Mixer Manufacturers Bureau.....	8
Universal Form Clamp Company.....	29
Water Seals, Inc.....	33
Wyandotte Chemicals Corporation.....	35

8
1
r
5
8
6
2
2
6
8
0
4
er
4
8
3
7
7
7
9
4
4
6
er
8
29
33
35
DN

2